

# TOWN OF CANTERBURY CONNECTICUT

## Site Preparation for Canterbury Public Works Building

### ADDENDUM NO. 1

January 14, 2013

#### CLARIFICATIONS OF "TOWN REQUIRED SPECIAL PROVISIONS"

##### 1. Clearing and Grubbing

All stumps excavated from the project area shall be removed from Town property and disposed of in a proper manner.

##### 2. Excavation

Topsoil that cannot be rendered usable for establishing a landscape cover on areas outside the paving limits shall be removed from Town property and disposed of in a proper manner.

Rock excavated from the site shall be removed from Town property and disposed of in a proper manner unless otherwise approved by the Town Engineer.

All newly formed embankments or filled excavations shall be compacted in lifts no greater than 12" deep. Compaction tests of each lift shall be conducted by an independent testing laboratory hired by the contractor prior to starting another lift.

#### CLARIFICATION OF "SCHEDULE OF CONSTRUCTION AND TIME OF COMPLETION OF THE WORK"

Work on this project shall begin as soon as possible after the Town issues a "Notice to Proceed", weather permitting. However, all work shall be completed no later than June 28, 2013.

#### CLARIFICATION OF "SURVEY BENCH MARK ELEVATIONS"

The Town shall be responsible for establishing at least two (2) bench marks adjacent to the project limits prior to commencement of construction.